

PROJECT:	_
TYPE:	_
PRODUCT:	_
APPROVED BY:	

PRODUCT FEATURES

- Intended for Hybrid Surgical Suites, Operating Rooms, Examination Rooms, and more
- Recessed or surface mount non-ferrous surgical troffer available 2x2 and 2x4 dimensions
- · Available with asymmetric acrylic lens
- Certified IP65 per IEC60598. Meets ISO 3 (Fed Std. 209E/ Class 1) Cleanroom rating. NSF2 Splash/Non-Food Zone.
- · This product is Made in America and complies with the Buy American Act (BAA) and the Build America, Buy America Act (BABAA)

















ORDERING INFORMATION

Example: SSS24-MRI-HA/OA-L440-90C-1C-A-UN-DM1

EXCITIBLE: 55524-MRI-HA/OA-L440-90C-IC-A-UN-DMI							
SS		MRI	HA	1			
Series	Mounting S = Surface R = Recessed	Nominal Size 22 = 2x2 24 = 2x4 *Nominal size. Dimensional data on Page 2.	MRI = Remote Driver. Remote Power Supply, ordered separately. Requires proper filter components supplied by others. Consult factory for additional information.	Housing HA = 16Ga. Alum Painted	Frame INSET (I) or OVERLAP (O) OA = 16Ga. Alum. Painted IA = 16Ga. Alum. Painted	Lumen Output* 12 = Low 14 = Standard 16 = Medium 18 = High 12 = Custom 13	Color Temp. 35 = 3500K 40 = 4000K 50 = 5000K

CRI 80C = 80 CRI 90C = 90 CRI	Circuits 1C = 1 Circuit 2C = 2 Circuits* *Allows for Inboard/Outboard control. 2C not available with L2 Lumen Output options.	Lens A = .125 Prismatic Acrylic E = .125 White Frosted Poly. S = .125 Asymmetric Acrylic and .080 White Frosted Acrylic diffuser*	Voltage 12 = 120V 27 = 277V 34 = 347V UN = Universal (120-277V)

POWER ENCLOSURE ORDERING INFORMATION

EXAMPLE: SSR24-PS-2-2C-DM

SS			PS			
Series	Mounting S = Surface R = Recessed	Size 22 = 2x2 24 = 2x4	PS =Power Enclosure* *Up to 8 drivers can be in a Power Enclosure depending on quantity of fixtures ordered. Consult factory for custom configurations. Configuration must be determined at time of order.	*Please refer to chart on page 5. Requires proper filtration components, by others. Each driver requires a filter.	Circuits 1C = 1 Circuit 2C = 2 Circuits* *Allows for Inboard/ Outboard control. 2C not available with L2 Lumen Output options.	Options DM = 0-10V dimming with 10-100% range DM1 = 0-10V dimming with 1-100% range



New Star Lighting

2225 W Pershing Rd, Chicago, IL 60609 (773) 847-1400 www.newstarlighting.com

Specifications and dimensions are subject to change without notice. For additional options and dimensional details, please consult your New Star Lighting representative.



SPECIFICATIONS

HOUSING: 16-gauge aluminum housing standard.

FRAME: Inset or overlapping doorframe available in aluminum. Frame held to housing via aircraft cable.

LENS: See lens options below. Inset and Overlapping frame uses a rail hold down system.

LED: Available in three color temperatures 3500K, 4000K and 5000K with maximum 3-step MacAdam variation allowance. Other color temperatures available, consult factory. Minimum 50,000 hours with 70% lumen maintenance in a 25°C ambient temperature, compliant with IES LM-80 testing standards.

ELECTRICAL: 120-277VAC 50/60HZ electrical input high power factor electronic, constant current driver (<20% THD, >0.90 PF). 0-10V dimming with 1-100% or 10-100% range. Step dimming options available.

FASTENERS: Stainless steel Philips flat head screws with captive cage nuts. Finish to match doorframe.

FINISH: White antimicrobial polyester powder coat finish following multi-stage iron phosphate pretreatment.

GASKET: Closed cell EPDM and closed cell silicone gaskets prevent air contaminants from entering the fixture. Gasketing seals lens to doorframe and doorframe to housing.

POWER ENCLOSURE: LED driver included - must be remote mount. Must order Power Enclosure separately. Consult factory for more information. MRI room EMI filter required, supplied by others.


MOUNTING: Surface (S) or Recessed (R) installation. Recessed mounting accommodates Grid and Flange installations. Recessed fixtures will be supplied with adjustable swing arms that can be used for Flange applications or taped to the side for Grid applications. Recessed install compatible with 1-1/2" and 15/16" Grid systems. Mounting for custom ceilings available, consult factory.

WARRANTY: 5 Year Warranty.


LABEL: Certified IP65 per IEC60598. Meets ISO 3 (Fed Std. 209E/ Class 1) cleanroom rating. NSF2 Splash/Non-Food Zone. This product was Made in America and complies with the Buy American Act (BAA) and the Build America, Buy America Act (BABAA).

DIMENSIONAL DATA


Fixture weight varies and is dependent upon chosen specifications. Consult factory for additional information. Average weight of the SSS24 is 48lb.



RECESSED MOUNTING (R): GRID & FLANGE



GRID COMPATIBILITY: SSR22: Spaced at 24" x 24" Centers SSR24: Spaced at 24" x 48" Centers



	А	В	С
SSS22	24.00″	3.94"	24.07"
SSS24	24.00"	3.94"	48.07"
SSR22	23.69"	4.00″	23.69"
SSR24	23.69"	4.00"	47.69"



PERFORMANCE DATA

*Data is with 80 CRI chip. LEDs are frequently updated therefore values may change without notice.

MODEL	ОИТРИТ	COLOR TEMP.	LUMENS DELIVERED	EFFICACY (Im/W)	INPUT POWER (W)
		3500K	3000	120	25
	L2 = LOW	4000K	3125	125	25
		5000K	3250	130	25
		3500K	6000	120	50
	L4 = STANDARD	4000K	6250	125	50
0000		5000K	6500	130	50
SS22		3500К	8625	115	75
	L6 = MEDIUM	4000K	9000	120	75
		5000K	9375	125	75
		3500К	11500	115	100
	L8 = HIGH	4000K	12000	120	100
		5000K	12500	125	100
		3500K	6000	120	25
	L2 = LOW	4000K	6250	125	25
		5000K	6500	130	25
		3500К	12000	120	50
	L4 = STANDARD	4000K	12500	125	50
SS24		5000K	13000	130	50
5524		3500K	17250	115	75
	L6 = MEDIUM	4000K	18000	120	75
		5000K	18750	125	75
		3500K	23000	115	100
	L8 = HIGH	4000K	24000	120	100
		5000K	25000	125	100



POWER ENCLOSURE: NUMBER OF DRIVERS PER FIXTURE

SERIES	SIZE	LUMEN OUTPUT	NUMBER OF DRIVERS PER FIXTURE
SS	22 = 2x2	L2 = LOW	1
		L4 = STANDARD	1
		L6 = MEDIUM	2
		L8 = HIGH	2
	24 = 2x4	L2 = LOW	1
		L4 = STANDARD	2
		L6 = MEDIUM	3
		L8 = HIGH	4



IMPORTANT SAFETY MEASURES

Power must be supplied by grounded New Star Remote Power Supply to ensure adequate EMI filtering. Remote Power Supply system must be ordered separately, and installed according to provided instructions.

- This must be installed in accordance with the applicable installation code by a person familiar with the construction and operation of the product and the hazards involved in a MRI environment
- · Disconnect power to all circuits before wiring fixture
- · Install in accordance with all national, state, and local codes
- · Remote Power Supply MUST be grounded
- · Failure to install unit on a mechanically sound surface may result in personal injury, physical damage, or potential fire hazard
- · Use installation procedures appropriate to a MRI environment and sensitive electronic equipment
- Read all fixture marketing and labels to ensure correct installation of the luminaire
- Supplemental instructions may be located on the luminaire, in addition to the instruction sheet provided by New Star, regarding orientation or mounting restrictions



SPECIFIER ACKNOWLEDGMENT

Contractor acknowledges and understands the requirements of installing New Star Lighting products prior to the installation. Please sign below before New Star Lighting releases your order.

Signature:	Date:
Print Name:	Project Name:
See next page for MRI installar	tion registration checklist



MRI INSTALLATION REGISTRATION CHECKLIST

Customer acknowledges that attached Installation Registration Checklist will be provided to the installer to sign and return to New Star Lighting after the installation is complete. Please fill out this form and return to your New Star Lighting Representative.

The warranty for your MRI installation will not go into effect until receipt of this signed registration checklist.

I certify that the lighting installation for the listed MRI suite is completed per the provided installation instructions and to the best of my abilities.

Please check off to denote status:

Installation instruction sheet for Remote Power Supply is read and followed.

Remote Power supply is located outside the shielded MRI exam room and grounded.

All dimming signals wiring is located outside the shielded MRI room.

Lighting system fully tested (including dimming operation if applicable) while MRI machine is in idle mode.

Lighting system fully tested (including dimming operation, if applicable) while MRI machine is in scan operation mode with the magnets fully activated.

If any of those steps cannot be completed or you need technical assistance, please contact your New Star Lighting Representative.

Electrical Contractor	Installation site
Name:	Project Name:
Phone:	City / State (Province):
Installation date:	Send the form to your New Star Lighting Representative.
New Star Lighting Representative:	
Date:	